*The 8th January* 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur division, up to 8th February 1898 for constructing a 1st Class Travellers' Bangalo at Mudgere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a 1st Class Travellers' Bangalo at Mudgere," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

DETAILED ABSTRACT ESTIMATE.

| *Items of work.* | *Per.* | *Quantity.* |
|---|---|---|
| Earthwork excavation and filling basement .. .. .. | C. yds. | 154 |
| Burnt stone in chunam (foundation and basement) including bond slabs .. | C. ft. | 4,837 |
| Burnt stone in mud do .. .. | " | 1,712 |
| Burnt brick in mortar superstructure do .. .. | " | 7,914 |
| Burnt brick in mud do .. .. .. .. | " | 4,095 |
| Arch work burnt brick in mortar .. .. .. .. | " | 275 |
| Coping with do as per plan .. .. . | R. ft. | 60 |
| Burnt stone slabs .. .. .. .. .. | S. ft. | 1,083 |
| Teak wood work wrought and put up .. .. .. .. | C. ft. | 392 |
| Jungle wood work (reserved) .. .. .. .. | " | 130 |
| Roofing with 1st class Mangalore tiles and teak reepers, &c., complete . | Sqrs. | 72·03 |
| Ridge tiles set in mortar including pointing .. .. .. | R. ft. | 191 |
| Flooring with concrete 6" thick and plaster over it .. .. .. | Sqr. | 2,857 |
| Do gravel and cowdung washing .. .. .. | " | 6·91 |
| Ventilating tiles .. .. .. .. .. | No. | 5 |
| Cornice in chunam as per plan .. .. .. .. | R. ft. | 100 |
| Plastering with chunam .. . .. . .. | Sqrs. | 140·48 |
| Do in mud and cowdung washing .. .. . | " | 48·67 |
| Pointing with chunam .. .. .. .. .. | " | 6·83 |
| White-washing 2 coats .. .. .. .. .. | " | 139·04 |
| Color washing 2 coats .. .. .. .. .. | " | 59·11 |
| Teak wood doors panelled with four shutters as per detail ($4\frac{1}{2}' \times 7\frac{1}{2}'$) including frames, hinges and runlock, &c., complete.. .. .. | S. ft. | 67 |
| Teak wood doors panelled with double shutters do ($4\frac{1}{2}' \times 7\frac{1}{2}'$) do .. | S. ft. | 540 |
| Do do (4′ × 7′) do .. | " | 112 |
| Do do ($3\frac{1}{2}' \times 6\frac{1}{2}'$) do .. | " | 91 |
| Teak wood windows with inside glazed shutters $4 \times 5\frac{1}{2}$ .. | " | 308 |
| Do do $3 \times 4\frac{1}{2}$ .. | " | 54 |
| Do ventilators wing glazed 4′ × 2′ including frames .. .. | Each. | 14 |
| Do circular $3\frac{1}{2}$ diameter .. .. | " | 4 |
| Jungle wood doors battened including frames ($3\frac{1}{2}' \times 6'$) lock, &c. .. .. | " | 3 |
| Do windows, wooden bars and shutters ($2 \times 2\frac{1}{2}$) frames .. .. | " | 2 |
| Do door small (3′ × 6′) including frames, &c. .. .. | " | 5 |
| Wood oiling .. .. .. .. .. | Sqrs. | 50·00 |
| Chocolate painting 2 coats .. .. .. .. | " | 22·90 |
| Teak wood eave boards ordinary .. .. .. .. | R. ft. | 560 |
| Tarring jungle wood work .. .. .. .. . | L. S. | .. |
| Bamboo matting (outer rind) .. .. .. .. | Sqrs. | 26·15 |
| Zinc sheets for valley .. .. .. .. .. | S. ft. | 216 |
| Constructing cisterns in the bath-rooms with burnt brick in chunam and concrete plaster .. .. .. .. .. | No. | 4 |
| Clearing site, levelling compound and putting hedges, opening approach roads and sundry works, &c., complete.. .. .. .. .. | .. | .. |

B. SUBBA RAO, *Offg. Executive Engr.*